

OFFICE OF THE PRINCIPAL
WOMEN'S TRAINING COLLEGE
NORTH GANDHI MAIDAN
PATNA UNIVERSITY, PATNA 800001

Website: wtcpu.org.in

EMERGENT NOTICE INVITING QUOTATION

Quotation No: 07/Nh/26

Date: 10-02-2026

NAME OF WORK: REPAIR AND PAINTING OF PASSAGES AT GROUND FLOOR & SPORTS SHADE IN WOMEN'S TRAINING COLLEGE, P.U. PATNA

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, Women's Training College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Women's Training College, Patna up to 3.00 p.m. on 17.02.2026
Place, Time & Date of opening quotation	Office of the Principal, Women's Training College, Patna at 3.30 p.m. on 17.02.2026

PRESCRIBED FORMAT

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
1	6.1.1 2/	Brick work with bricks of class designation-100A in foundations and plinth in : Cement mortar 1 :4 (1 cement: 4 coarse sand)	0.5	Cum	Cum		
2	6.3A	Extra for Brick work in superstructure above plinth level upto floor V cum	0.5	Cum	Cum		
3	13.12 .2	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4(1 cement: 4 coarse sand)	7	Sqm	Sqm		
4	14.1.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement :4 fine Sand)	84	Sqm	Sqm		
5	13.80	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repari scratches etc. complete.	869	Sqm	Sqm		

S.N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
6	13.80 A.2	Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	870	Sqm	Sqm		
7	2.35 1	Supplying chemical emulsion in sealed containers including delivery as specified Chlorpyriphos /Lindone emulsifiable concentrate of 20%	2	Litre	Litre		
8	13.46 .1	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	953	Sqm	Sqm		
9	13.93 .1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	204	Sqm	Sqm		
10	4.1.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, post. struts,buttresses, string or lacing courses, parapets, coping,bedblocks, anchor blocks, plin windowsills, fillets etc. upt floor five level excluding the cost of centring,shuttering and finishing:1:1.5:3	0.3	Cum	Cum		
11	9.48. 2	Providing and fixing M.S. grills of required pattern in frames of windowsetc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings/ wooden frames with rawl plugs screws etc	34	Kg	Kg		
12	S.O.R	Carraige of materials :					
	a	Designation 100 A Bricks from 8 Km distance of surface road and an additional lead of 1 Km kutcha road from site.	210	No	%0No		
	b	Sone sand from Koelwar, 45 Km distance of surface road.	2	Cum	Cum		

PKA

S.N	Code No	Description	Quantity		Unit	Rate	Amount	
						(Rs.)		
13		Providing following materials of approved quality for covering expansion joints and dismantling wall for proposed ventilators, as per direction of Engineer-in-charge						
a	2631	A.C.P. of 4 mm thickness	2.11	Sqm	Sqm			
b	OL71	Skilled Labour	2	Lab/Da y	Lab/Da y			
c	o458	plastic sleeves for screw	25	No	Each			
d	o635	Brigh finish or black enameled mild steel screws 50 mm	25	No	% no			
14	S.O.R	Price difference of materials for Patna urban area: Ordinary Portland cement.	18	Bag	Bag			
15		Reserved price for any other un seen work.	1	L.S.	L.S.	4147	4147	
TOTAL								

TERMS & CONDITIONS

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Women's Training College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, Women's Training College, Patna @ 2% i.e.Rs.5,800/- is essentialy required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 1 month after receiving work order.
- 3 Rate and amount of serial number 15 has been previously fixed as Rs.4147/-
- 4 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 5 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 6 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 7 The undersignd reserve the right to accept or reject any or all the quotations without assigning any reason.
- 8 All disputes, what so ever shall be referred to the sole arbitration of the Principal, Women's Training College, Patna and her decision shall be final and binding on the agency.

H. Khan
10/2/2026
PRINCIPAL

**WOMEN'S TRAINING COLLEGE
PATNA**