

OFFICE OF THE PRINCIPAL
WOMEN'S TRAINING COLLEGE
NORTH GANDHI MAIDAN
PATNA UNIVERSITY. PATNA 800001
Website: wtcpu.org.in

EMERGENT NOTICE INVITING QUOTATION

Quotation No: 08/Wk/26

Date: 10-02-2026

NAME OF WORK: REPAIR AND RE FLOORING WORK OF 3 NUMBERS OF ROOMS (ROOM NUMBER 3, 9 AND 12) AT GROUND FLOOR, WOMEN'S TRAINING COLLEGE, P.U. PATNA

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

| | |
|--|---|
| Designation of officer inviting quotation | Principal, Women's Training College, Patna |
| Place, Time & Date of receiving of quotation | Office of the Principal, Women's Training College, Patna up to 3.00 p.m. on 17.02.2026. |
| Place, Time & Date of opening quotation | Office of the Principal, Women's Training College, Patna at 3.30 p.m. on 17.02.2026. |

PRESCRIBED FORMAT

| S.N. | Code No | Description | Quantity | | Unit | Rate | Amount |
|------|---------|---|----------|-----|------|------|--------|
| | | | | | | (Rs) | |
| 1 | OL71 | Providing skilled labours for chisseling existing P.S. Flooring and other necessary work, as per direction of Engineer-in-charge. | 2 | Day | Day | | |
| 2 | 4.1.2 | Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering-all work upto plinth level. 1:1.5:3(1Cement :1.5 coarse sand :3 graded stone aggregate 20 mm nominal size) | 2.7 | Cum | Cum | | |
| 3 | 11.41.2 | Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08 % and conforming to IS : 15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1cement : 4 coarse sand) including grouting the joint with white cement and matching pigments etc., complete. Size of Tile 60x60 cm | 54 | Sqm | Sqm | | |
| 4 | 15.56. | Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. | 61 | Sqm | Sqm | | |


| S.N. | Code No | Description | Quantity | | Unit | Rate | Amount |
|------|-----------|---|----------|-------|-------|-------|--------|
| | | | | | | (Rs.) | |
| 5 | 11.46.2 | Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600 x 600 mm | 7 | Sqm | Sqm | | |
| 6 | 14.1.1 | Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement :4 fine Sand) | 25 | Sqm | Sqm | | |
| 7 | 13.80. | Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repair scratches etc. complete. | 266 | Sqm | Sqm | | |
| 8 | 13.80 A.2 | Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. | 345 | Sqm | Sqm | | |
| 9 | 2.35.1 | Supplying chemical emulsion in sealed containers including delivery as specified Chlorpyrifos /Lindone emulsifiable concentrate of 20% | 3 | Litre | Litre | | |
| 10 | 13.46.1 | Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) | 345 | Sqm | Sqm | | |
| 11 | 9.46 | Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete:25 mm dia metre | 15 | m | m | | |
| 12 | 13.93.1 | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work | 44 | Sqm | Sqm | | |
| 13 | 26.29.1 | Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-In-Charge. Bars up to 12 mm dia. | 55 | m | m | | |

PKA

| S N. | Code No | Description | Quantity | | Unit | Rate | Amount | |
|--------------|---------|---|----------|------|------|-------|--------|--|
| | | | | | | (Rs.) | | |
| 14 | 13.31.1 | Rough cast plaster with a mixture of sand and gravel or crushed stone from 2.36 to 12.5 mm nominal size dashed over and including the fresh plaster in two layers, under layer 12 mm cement plaster 1:5(1 cement:5 coarse sand) and top layer 10 mm cement plaster 1:3(1 cement:3 coarse sand) mixed with 10% finely grounded hydrated lime by volume of cement: | 26 | Sqm | Sqm | | | |
| 15 | 13.12.2 | 15 mm cement plaster on rough side of single or half brick wall of mix: 1:4(1 cement: 4 coarse sand) | 32 | Sqm | Sqm | | | |
| 16 | o111 | Providing Carpenter for minor repair of wooden doors and windows, as per direction of Engineer-in-charge. | 3 | Day | Day | | | |
| 17 | 14.5.1 | Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm | 1.5 | Sqm | Sqm | | | |
| 18 | S.O.R. | Carraige of materials : Sone sand from Koelwar, 45 Km distance of surface road. | 5 | Cum | Cum | | | |
| 19 | S.O.R. | Price difference of materials for Patna urban area: Ordinary Portland cement. | 47 | Bag | Bag | | | |
| 20 | | Reserved price for any other un seen work. | 1 | L.S. | L.S. | 4850 | 4850 | |
| TOTAL | | | | | | | | |

Terms and conditions:

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Women's Training College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, Women's Training College, Patna @ 2% i.e.Rs. 4,902/- is essentialy required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 2 month after receiving work order.
- 3 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 4 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 Rate and amount of serial number 20 has been previously fixed as Rs.4850/-
- 7 The undersignd reserve the right to accept or reject any or all the quotations without assigning any reason.
- 8 All disputes, what so ever shall be referred to the sole arbitration of the Principal, Women's Training College, Patna and her decision shall be final and binding on the agency.


 N. Khan
 PRINCIPAL
 WOMEN'S TRAINING COLLEGE
 PATNA